Sharjah-UAE
P.O. Box: 46298
Tel.: 06-5397 442
Fax: 06-5397 443

lifeline
TRADING COMPANY L.L.C.

خط الحياة
للتجارة ش . ذ . م . م .

Dubai - UAE
P.O. Box: 46298
info@lifelineuae.com
www.lifelineuae.com

LT-4955-6/BT/1122/QT/JO
20.02.2023

M/s. GINCO Contracting Co. L.L.C
P.O Box. 1809, Sharjah UAE.

Tel.: 06 553 1532
Fax : 06 553 1545

Attention	:	**Mr. Vaibhav Goel**
Project	:	**Construction of G+1 Villa**
Location	:	**Plot No. 1 @ Beach Palace, Ajman**
Client	:	**M/s. H.H.SH. Rashid Bin Humaid Al Nuaimi**
Consultant	:	**Eng. Adnan Saffarini**
Main Cont.	:	**M/s. GINCO Contracting Co. LLC**
MEP Cont.	:	**M/s. GINCO Electrical & Sanitary Contracting Co. LLC**
Subject	:	**Quotation for Cooling System & Circulation Pumpset.**

Dear Sir,

With reference to the above mentioned project, we would like to give our best prices, delivery terms and conditions for **Supply,Installation & Commissioning of Cooling System, Supply & Commissioning Circulation Pump Set.**

Kindly refer to the attached sheet for details

Terms & Conditions :-

Delivery	:	As mentioned.
Payment	:	**40% advance along with the order, 50% CDC upon delivery, balance 10% upon Installation, Testing & Commissioning. (Testing & Commissioning should be done with in 3 months from the date of delivery)** (Cheque copy to be send before delivery)
Validity	:	2 Weeks from the date of Quotation.
Warranty	:	As mentioned. (Operational error damages will not cover under Warranty).

We hope this will meet with your approval and waiting for your valuable order.

Yours truly,

***For,* life line Trading Co. L.L.C.**
Benny Thelappilly (055 – 97 92 895)
Manager – Sanitary Division
benny.lifeline@gmail.com

Shajeer Kakkat
Senior Manager
055 979 2897 / shajeer@lifelineuae.com

Sharjah-UAE
P.O. Box: 46298
Tel.: 06-5397 442
Fax: 06-5397 443

lifeline
TRADING COMPANY L.L.C.

خط الحياة
للتجارة ش . ذ . م . م .

Dubai - UAE
P.O. Box: 46298
info@lifelineuae.com
www.lifelineuae.com

LT-4955-6/BT/1122/QT/JO
20.02.2023

SL	Description of Items	Qty	UNIT PRICE	TOTAL AMOUNT
1	***Supply, Installation & Commissioning of Cooling System:*** **12.5 Ton Water Chiller 380 V, 3 Ph, 50HZ** **(SABCON-UAE)** Compressor : Copeland-USA Shell body : Stainless Steel Electric Power : 17 kW Tube inside pipe : Copper Refrigerant : **R – 407**	1 No.	38,000.00	**38,000.00**
	Warranty : 1 year from the date of TOC (TOC shall be considered 3 months from the date of Invoice)			
	Delivery : 2 weeks after getting PO and Advance payment.			
	TOTAL AMOUNT FOR CHILLER IN AED.			38,000.00
	5%VAT IN AED.			1,900.00
	TOTAL AMOUNT INCLUDING 5%VAT IN AED.			**39,900.00**
2	**CIRCULATION PUMP SET FOR CHILLER :-** **(1D + 1S + Control Panel + 24 Hrs Timer)** (Supply & Commissioning) **Pump Brand : XYLEM GOULDS – ITALY** **Model : 5HM03N04T** Horizontal Multi Stage (**SS316**) Type 1.75 L/s @ 15 mtr 0.40 kW / 0.53 HP, 3 ph – 50 Hz, 2900 Rpm, 2 Pole Inlet & Outlet : 1 ¼ " x 1 ¼ " Header : **PPR** Pipe Works	01 No	10,500/-	**10,500/-**
	Warranty : 1 year + 4 years extended (Total 5 years from the date of TOC) (TOC shall be considered 3 months from the date of Invoice)			
	Delivery : 8 – 10 weeks after getting PO and Advance payment.			
	TOTAL AMOUNT FOR CIRCULATION PUMP SET IN AED.			10,500.00
	5%VAT IN AED.			525.00
	TOTAL AMOUNT INCLUDING 5%VAT IN AED.			**11,025.00**

TOTAL AMOUNT FOR CHILLER + CIRCULATION PUMP (INCLUDING 5%VAT) IN AED.	**50,925.00**
FINAL DISCOUNTED PRICE (INCLUDING 5%VAT) IN AED.	**49,000.00**

LIFE LINE TR. CO. L.L.C. SHARJAH - U.A.E. P.O. Box: 46298

Sharjah-UAE
P.O. Box: 46298
Tel.: 06-5397 442
Fax: 06-5397 443

lifeline
TRADING COMPANY L.L.C.

خط الحياة
للتجارة ش . ذ .م .م .

Dubai - UAE
P.O. Box: 46298
info@lifelineuae.com
www.lifelineuae.com

LT-4955-6/BT/1122/QT/JO
20.02.2023

Scope of work:-

1. Supply and Installation with commissioning of Chiller & pumpset
2. Installation & commissioning with standard PVC pipe line work chiller to tank and tank to chiller (Upto less than 5 mtr)
3. Electrical wiring from isolator to chiller & Pumpset

Exclusions:

1. Insulation of Water Tank & Water supply piping on Roof
2. Existing tank water clearing
3. Piping works from main supply line to water tank
4. Making foundation and protection cover for the units
5. Permission from authorities.
6. Loading, unloading the equipment & shifting to roof.
7. All types of Civil, Plumbing and Electrical works other than mentioned in our scope of work.

We hope this will meet with your approval and waiting for your valuable order.

Yours truly,

***For,* life line Trading Co. L.L.C.**

Benny Thelappilly (055 – 97 92 895)
Manager – Sanitary Division
benny.lifeline@gmail.com

Shajeer Kakkat
Senior Manager
055 979 2897 / shajeer@lifelineuae.com